BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT51695

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/03/2022-23, Date: 21-05-2022

Name of Work:Improvements to Roads and Drains at Deshabandunagara and Surrounding areas in Ward No. 09 (Vidyaranyapura).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAGOOR LOKANADHA REDDY ( )	
				In Figures	In Words
1	291.06	Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)	Sqm	116.87	Rupees One Hundred Sixteen and Eighty Six Paise Only
2	430.05	Earth work excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. (PWD SR 21-22 Vol -I Pg No 5 item no 1.4.1)	Cum	214.83	Rupees Two Hundred Fourteen and Eighty Three Paise Only
3	124.74	Providing granite slabs of selected quality roughly dressed having a size of 7.5cms thick and fixed in cement mortar (1:6) including fixing curing ete., complete.(P.No.27,I.No.5.31.1)	Sqm	779.10	Rupees Seven Hundred Seventy Nine and Ten Paise Only
4	56.73	Providing and laying in position plain cement concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. (PWD SR 2021-2022 Vol -I Pg 15 item no 2.1.3)	Cum	6643.56	Rupees Six Thousand Six Hundred Forty Three and Fifty Six Paise Only
5	111.69	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. (The cost of steel reinforcement & formwork to be paid separately) (PWD SR 21-22 Vol -I Pg 17 item no 2.4.2)	Cum	7586.96	Rupees Seven Thousand Five Hundred Eighty Six and Ninety Six Paise Only
6	6.96	Supplying, Fitting and Placing un-coated TMT bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. MORTH Specification NO.1600&2200 (PWD SR 21-22 Vol -III Pg 99 item no 13.1)	tonne	119345.00	Rupees One Hundred Nineteen Thousand Three Hundred Forty Four and Ninety Nine Paise Only
7	568.2	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2453.85	Rupees Two Thousand Four Hundred Fifty Three and Eighty Five Paise Only
8	21.6	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge	Sqm	5688.90	Rupees Five Thousand Six Hundred Eighty Eight and Ninety Paise Only
9	16.17	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. 1;2;4(The cost of steel reinforcement & formwork to be paid separately) (PWD SR 2021-22 Vol -I Pg 17 item no 2.4.1)	Cum	7040.88	Rupees Seven Thousand Forty and Eighty Eight Paise Only

N. Lokanadha Reddy
Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NAGOOR LOKANADHA REDDY ( )	
				In Figures	In Words
10	246.4	Providing and constructing load bearing wall with Solid Concrete blocks of size 400x150x200mm having block density more than 1800kg/m3 and minimum compressive strength of 4.00 N/mm2 conforming to IS 2185 (Part - I) - 2005 and constructed with CM 1:4 as per IS 2572:2005 including cost of all materials, labour, scaffolding and curing, usage charges of machinery etc complete as per specifications. (PWD SR 2021-22 Vol -II Pg 17 item no 6.33)	Sqm	1232.39	Rupees One Thousand Two Hundred Thirty Two and Thirty Eight Paise Only
11	430.05	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. (Tipper 14 m3) (PWD SR 2021-22 Vol-III Page No.3, Item No.1.1C)	Cum	81.40	Rupees Eighty One and Forty Paise Only
12	550.46	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km (PWD SR 2021-22 Vol-III Page No.3, Item No.1.4B)	t.Km	115.50	Rupees One Hundred Fifteen and Fifty Paise Only

N. Lokanadha Reddy

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2022-23/OW/WORK_INDENT51696

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/03/2022-23, Date: 21-05-2022

Name of Work:Improvements to Roads and Drains at Yerappa Garden in Ward No. 09 (Vidyaranyapura).

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MAHESH C (K R CONSTRUCTIONS..)	
				In Figures	In Words
1	5.04	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead I By Manual Means B Cement Concrete Grade M-15 & M-20 and as per the directions of the Engineer-in-charge of the work .	Cum	844.31	Rupees Eight Hundred Forty Four and Thirty Paise Only
2	9.48	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead (iii) Dismantling Stone Masonry B Rubble stone masonry in cement mortar. and as per the directions of the Engineer-in-charge of the work .	Cum	555.56	Rupees Five Hundred Fifty Five and Fifty Five Paise Only
3	584.91	Earth work Excavation by manual means for drains,canals, waste weir, draft, approach channels, key trenches, foundation of bridges and such simillar works in all kinds of soils , as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter, excavated surface leveled and sides neatly dressed disposing off the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools & other appurtenaces required to complete the work. and as per the directions of the Engineer-in-charge of the work .	Cum	214.83	Rupees Two Hundred Fourteen and Eighty Three Paise Only
4	71.18	Providing and laying in position Plain Cement Concrete Mix 1:3:6 (M10) for levelling course for all works in foundation. Using 40 mm nominal size graded crushed coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machineries, curing, and all the other appurtenances required to complete the work as per technical specifications. and as per the directions of the Engineer-in-charge of the work .	Cum	6643.56	Rupees Six Thousand Six Hundred Forty Three and Fifty Six Paise Only
5	139.06	Providing and laying in position Reinforced Cement Concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. and as per the directions of the Engineer-in-charge of the work .	Cum	7586.96	Rupees Seven Thousand Five Hundred Eighty Six and Ninety Six Paise Only
6	8.92	Supplying, Fitting and Placing TMT Fe550 bar Reinforcement in sub-structure complete as per Drawing and Technical Specifications. and as per the directions of the Engineer-in-charge of the work .	tonne	119345.00	Rupees One Hundred Nineteen Thousand Three Hundred Forty Four and Ninety Nine Paise Only
7	893.43	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of all materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. and as per the directions of the Engineer-in-charge of the work .	Sqm	2453.85	Rupees Two Thousand Four Hundred Fifty Three and Eighty Five Paise Only
8	48.24	Providing and Fixing pre cast Covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.and as per the directions of the Engineer-in-charge of the work .	Sqm	5688.90	Rupees Five Thousand Six Hundred Eighty Eight and Ninety Paise Only
9	485.78	Earth work in surface Excavation by mechanical means for lowering & leveling the ground for all works other than foundation in all kinds of soils & upto depth not exceeding 300mm as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, removal of stumps and other deleterious matter including dressing of excavated surfaces, disposing off or levelling the excavated earth or sorting & stacking the selected earth for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage of machinery & other appurtenances required to complete the work. and as per the directions of the Engineer-in-charge of the work .	Cum	75.08	Rupees Seventy Five and Seven Paise Only

Signature of Contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MAHESH C (K R CONSTRUCTIO ..)	
				In Figures	In Words
10	1119.15	Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications. and as per the directions of the Engineer-in-charge of the work .	Sqm	6.68	Rupees Six and Sixty Seven Paise Only
11	167.87	Construction of Granular Sub-Base of required grading as per design mixing in a mechanical mix plant at OMC, carriageof mixed Material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete and as per the directions of the Engineer-in-charge of the work .	Cum	2710.79	Rupees Two Thousand Seven Hundred Ten and Seventy Eight Paise Only
12	257.4	Providing, laying, spreading and compacting graded stone aggregate to Wet Mix Macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver/grader in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density Specification and as per the directions of the Engineer-in-charge of the work .	Cum	2765.07	Rupees Two Thousand Seven Hundred Sixty Five and Seven Paise Only
13	1119.15	.Cleaning the existing WBM Road surface including removing of binding materials and other foreign matter with wire brushes and small picks sweeping with brooms or soft brushes and finally dusting with old gunny bags and bar or compressed air to receive bituminous treatment including cost of all materials, labhour, HOM of machineries complet as per specifications.and as per the directions of the Engineer-in-charge of the work.	Sqm	22.26	Rupees Twenty Two and Twenty Six Paise Only
14	1119.15	Providing and applying Primer Coat with SS1 grade Bitumen Emulsion on prepared surface of granular base includingcleaning of road surface and spraying primer at the rate of 0.90 kg per m2 using mechanical means Specification and as per the directions of the Engineer-in-charge of the work .	Sqm	48.40	Rupees Forty Eight and Forty Paise Only
15	55.96	Providing and laying Dense Graded Bituminous Macadam with 40/60 TPH capacity HMP using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 4.5 per cent by weight of total mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per specification and as per the directions of the Engineer-in-charge of the work .	Cum	11421.80	Rupees Eleven Thousand Four Hundred Twenty One and Seventy Nine Paise Only
16	1119.15	Cleaning the existing black topped surface with brooms,soft brushes and finally dusting with old gunny bags and/or compressed air to receive bituminous treatment including cost of all materials,labhour, HOM of machineries complete as per specifications.and as per the directions of the Engineer-in-charge of the work .	Sqm	5.30	Rupees Five and Thirty Paise Only
17	1119.15	Providing and applying Tack Coat with RS1 Bituminous Emulsion using emulsion pressure distributor at the rate of 0.25 kg/m2 on the prepared bituminous surface cleaned with mechanical broom Specification and as per the directions of the Engineer-in-charge of the work .	Sqm	16.50	Rupees Sixteen and Fifty Paise Only
18	44.77	Providing and laying Bituminous Concrete with 40/60 TPH capacity hot mix plant using crushed aggregates of specified grading, premixed with bituminous binder VG-30, @ 5.4 percent of mix and filler, transporting the hot mix to work site, laying with mechanical paver finisher to the required grade,level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per specification and as per the directions of the Engineer-in-charge of the work .	Cum	13318.31	Rupees Thirteen Thousand Three Hundred Eighteen and Thirty Paise Only
19	44.28	Road Marking with Hot Applied Thermoplastic Compound with Reflectorising Glass Beads on Bituminous Surface Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads @ 250 g/ m2 area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35:2015.The finished surface to be level, uniform and free from streaks and holes. Specification and as per the directions of the Engineer-in-charge of the work .	Sqm	552.09	Rupees Five Hundred Fifty Two and Nine Paise Only
20	76.24	Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 m3 in volume and stock piling at designated locations and disposal of dismantled materials and stacking serviceable and unserviceable materials separately Specification and as per the directions of the Engineer-in-charge of the work .	Cum	487.41	Rupees Four Hundred Eighty Seven and Forty One Paise Only
21	57.18	Construction of Dry Lean Cement Concrete Sub- base over a prepared sub-grade with coarse and fine aggregate conforming to IS: 383, the size of coarse aggregate not exceeding 25 mm,aggregate cement ratio not to exceed 15:1, aggregate gradation after blending to be as per table 600-1, cement content not to be less than 150 kg/ m3 , optimum moisture content to be determined during trial length construction, concrete strength not to be less than 10 Mpa at 7 days, mixed in a batching plant, transported to site, laid with a paver with electronic sensor, compacting with 8-10 t vibratory roller, finishing and curing. Specification and as per the directions of the Engineer-in-charge of the work .	Cum	4846.38	Rupees Four Thousand Eight Hundred Forty Six and Thirty Eight Paise Only

Signature of Contractor

Executive Engineer

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬ್ಯಾಟರಾಯನಪುರ ವಿಭಾಗ
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of MAHESH C (K R CONSTRUCTIONS..)	
				In Figures	In Words
22	57.18	Providing and constructing un-reinforced plain Cement Concrete Pavement, thickness as per design, over a prepared sub base, with 43 grade cement or any other type as per Clause 1501.2.2 M30 (Grade), coarse and fine aggregates conforming to IS:383, maximum size of coarse aggregate not exceeding 25 mm, mixed in a concrete mixer of not less than 0.2 cum capacity and appropriate weigh batcher using approved mix design, laid in approved fixed side formwork (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the formwork as per drawing), spreading the concrete with shovels, rakes, compacted using needle, screed and plate vibrators and finished in continuous operation including construction joints, , primer, sealant , curing of concrete slabs for 14- days, and water finishing to lines and grade as per drawing and technical specification clause 1501 with all lead, lifts, loading & unloading charges, cost and conveyance of all materials, labour, equipments etc., and as per the directions of the Engineer-in-charge of the work .	Cum	7896.74	Rupees Seven Thousand Eight Hundred Ninety Six and Seventy Three Paise Only
23	101.9	Cutting transverse contraction joints 3 to 4 mm wide and depth 60mm in concrete slab using concrete cutting machine with diamond studded saw within 48 hours of casting of bay / slab etc. complete including subsequent widening of the groove 8 to 10 mm. wide at top having depth of 15 mm. and as per the directions of the Engineer-in-charge of the work .	m	77.00	Rupees Seventy Seven Only
24	101.9	Providing to contraction joints polysuphide sealent (Pouring grade) confirming to BS : 5212 - 1989 into sawed groove widened at top for sealent reservoir of specified size and shape as per detailed drawing including fixing Polyethylenefoam backer rod of required diameter (approx. 25% larger than the initial 3 mm.to 4 mm. joint) overlaid with bond breaking tape as per detailed drawing. Item includes cleaning the joints with water jet / air compressor and allowing joint to become thoroughly dry before sealent is applied and applying primer. (A) Contraction and longitudinal joints (15 mm. deep x 8mm.wide). Specification and as per the directions of the Engineer-in-charge of the work .	m	181.50	Rupees One Hundred Eighty One and Fifty Paise Only
25	1045.3	Loading and Unloading of Stone Boulder/Stone aggregates/ Sand/Kankar/Moorum. and as per the directions of the Engineer-in-charge of the work .	Cum	81.40	Rupees Eighty One and Forty Paise Only
26	1337.99	Cost of Haulage Excluding Loading and Unloading Taking output 18 t load and lead 10 km = 180 t.km and as per the directions of the Engineer-in-charge of the work .	t.Km	121.28	Rupees One Hundred Twenty One and Twenty Seven Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92